Innovation Solutions for Renewable Future

MECREGEN™

MECREGEN / Tri-Internal Energy System

Engineering Validation & Technical Feasibility Report

Electromagnetic Reciprocating Engine • TIES™ Architecture • P1/P2/P3 Energy Balance

September 2026

PREPARED BY:

Mr. Kala Butler
Founder & CEO
Sekou Industries
kbutler@SekouIndustries.com

COMPANY
Sekou Industries Inc.
Holding Company
www.SekouIndustries.com
info@SekouIndustries.com

SUBSIDIARY
MECREGEN Group Inc.
MECREGEN Holding Company
www.MECREGENgroup.com
info@MECREGENgroup.com

BASE PRODUCT
MECREGEN
Tri-Internal Energy System
www.MECREGEN.com
info@MECREGEN.com

ENGINEERING REVIEW STATUS: The MECREGEN architecture is technically plausible as an electromagnetic reciprocating motor-generator system. Quantitative claims involving self-sustaining operation, continuous net export power, horsepower, efficiency, and MW-scale performance require calibrated physical prototype testing and complete energy-balance reconciliation before independent validation.

Table of Contents

1. Executive Engineering Assessment 1
2. System Architecture Reviewed 1
3. Magnetic Chamber Validation 1
4. Mechanical and Crankshaft Validation 2
5. Magnetic / Hybrid Bearing Feasibility 2
6. Generator and Electrical System Validation 3
7. P1 / P2 / P3 Configuration Review 3
8. Conservation-of-Energy and Energy-Balance Validation 4
9. Review of the 5,200 hp Example 5
10. Thermal, Electrical and Mechanical Losses 5
11. Controls and Timing Feasibility 6
12. Prototype Instrumentation Requirements 6
13. Required Validation Test Sequence 7
14. Independent Validation Criteria 7
15. Scaling and Commercial Feasibility 8
16. Overall Technical Feasibility Finding 8
17. Professional Reliance and Limitation 9
18. Claim Validation Matrix 9
19. Prototype Acceptance Checklist 9
20. Engineering Reviewer Sign-Off Template 10
21. Documentation Basis 10

1. Executive Engineering Assessment

This report evaluates MECREGEN™ (Mechanical Energy Conversion Renewable Generation) as an integrated electromechanical system. The review considers the Electromagnetic Reciprocating Engine (ERE), Tri-Internal Energy System™ (TIES), Magnetic Chamber, crankshaft energy conversion, power generation, P1/P2/P3 configurations, controls, losses, prototype testing, and validation requirements.

The fundamental conversion chain—electrical energy to electromagnetic field energy, magnetic force, reciprocating mechanical motion, crankshaft rotation, and optional electrical generation—is consistent with established engineering mechanisms. The architecture can therefore be advanced through normal mechanical, electrical, magnetic, controls, and test engineering.

The principal unresolved quantitative question is the complete sustained energy balance. Regeneration, flywheel inertia, and permanent magnets can convert, store, or redirect energy, but do not by themselves establish an independent continuous energy source. Claims of sustained internal operation plus net external output require synchronized measurement of every material energy input, output, storage change, and loss.

2. System Architecture Reviewed

TIES comprises three principal subsystems: Magnetic Chamber System, Crankshaft Energy Conversion System, and Power Generation System. Supporting systems include storage/external supply, power electronics, sensing, controls, thermal management, bearings/guidance, structural frame, protection, and data acquisition.

The primary pathway is: Electrical Energy → Electromagnetic Field Energy → Magnetic Force → Linear Mechanical Motion → Rotational Mechanical Power → Optional Generator/Alternator → Electrical Energy.

3. Magnetic Chamber Validation

The Magnetic Chamber operating principle is supported in principle by established electromagnetic actuation. Controlled electromagnets can develop position-dependent force, and electronic commutation can coordinate that force with reciprocating/crankshaft position.

Actual performance depends on air gap, magnetic geometry, coil ampere-turns, permanent-magnet properties, core saturation, leakage flux, inductance, resistance, back-EMF, switching waveform, hysteresis, eddy currents, temperature, and alignment. A general relationship is $F(x,I) = \partial W_m(x,I)/\partial x$. Finite-element analysis should be correlated with calibrated static and dynamic force mapping.

4. Mechanical and Crankshaft Validation

Reciprocating force can be converted to crankshaft torque through established slider-crank mechanics. Shaft power is $P_{shaft} = \tau\omega$, where $\omega = 2\pi(RPM)/60$. Torque is angle-dependent and must be evaluated across the operating cycle.

Rotational inertia stores kinetic energy, $E_k = \frac{1}{2}J\omega^2$, which can smooth torque and redistribute energy across a cycle. It does not create energy. Validation should include torque, RPM, crank angle, vibration, bearing loads, temperature, alignment, fatigue, structural response, wear, and overspeed considerations.



5. Magnetic / Hybrid Bearing Feasibility

Magnetic or hybrid bearing concepts are technically plausible methods for reducing mechanical contact, friction, and wear. Practical implementation requires stability and rotor-dynamic analysis, stiffness/damping characterization, backup bearings where needed, fault behavior, thermal assessment, and measurement of any system-level efficiency benefit.



6. Generator and Electrical System Validation

A generator or alternator can convert available shaft power to electricity according to Pgen, out = Pshaft, in × ηg. Electrical validation should include true real power, voltage/current waveforms, power factor where applicable, harmonics, generator efficiency, excitation, power electronics, rectification/inversion, protection and cooling.

All coil drivers, controls, pumps/fans, and other auxiliaries must be included in system input accounting.



7. P1 / P2 / P3 Configuration Review

P1 — Battery-to-Starter: stored electrical energy supplies the system. It is the preferred baseline for characterizing electromechanical conversion.

P2 — Battery-to-Alternator/Starter: battery energy initiates operation, and shaft energy may be recovered through an alternator/starter. This is regenerative operation. Sustained performance depends on total energy balance and losses.

P3 — Battery-to-Generator Head/Starter: startup is supported by storage, and the generator head may later provide electrical power to internal and external loads. Continuous external output must be determined after all internal demand, losses, and storage changes are measured.

P2 and P3 are technically plausible motor-generator arrangements; topology alone does not establish self-sustaining or net-positive operation.



8. Conservation-of-Energy and Energy-Balance Validation

The system boundary must include every external electrical input, generator output, mechanical output, battery/storage change, auxiliary load, cooling load, and significant stored-energy change.

Energy is evaluated over time using $E = \int P(t)dt$. A useful accounting framework is $E_{net} = E_{generator,\,out} + E_{mechanical,\,out} - E_{external,\,in} - \Delta E_{storage}$, using an explicitly defined sign convention and including auxiliary and loss terms.

A simplified closed motor-generator loop has $P_{return} = P_{in} \times \eta_{motor} \times \eta_{generator}$ before additional losses. Because real conversion efficiencies are below unity, a sustained useful output requires a corresponding external or stored energy source. Formal validation must reconcile the measured result with conservation of energy within the combined uncertainty budget.



9. Review of the 5,200 hp Example

MECREGEN documentation has included an example of approximately 5,200 hp total mechanical output, approximately 1,560 hp allocated to generator/system requirements, and approximately 3,640 hp remaining for productive work. Using 1 hp ≈ 0.7457 kW, these correspond to approximately 3.88 MW, 1.16 MW, and 2.71 MW.

The arithmetic is consistent. The underlying 5,200 hp value should remain identified as a design/modeling value unless calibrated torque and RPM measurements demonstrate it while all electrical inputs, storage changes, and auxiliary loads are simultaneously recorded.



10. Thermal, Electrical and Mechanical Losses

Validation must quantify winding I^2R heating, semiconductor conduction/switching losses, magnetic hysteresis, eddy currents, leakage flux, inductive/back-EMF effects, bearing/guide friction, windage, vibration, structural deformation, generator losses, power-conversion losses, battery charge/discharge losses, cooling loads and controls.

Testing should continue long enough to reach representative thermal conditions. Short tests can be distorted by temporary kinetic, electrical, battery, and thermal energy storage.



11. Controls and Timing Feasibility

Crank-position-controlled electromagnetic switching is technically feasible. The controller should manage startup, commutation, current regulation, speed/load response, fault detection, overcurrent, overvoltage, overtemperature, overspeed, emergency stop, and safe shutdown.

Timing values should be optimized and validated across speed, load, and temperature. Proposed TDC/BDC or angular cutoff values are engineering parameters requiring experimental confirmation rather than universal efficiency guarantees.



12. Prototype Instrumentation Requirements

Recommended instrumentation includes precision power analyzers; calibrated voltage/current transducers on all material energy paths; shaft torque transducer; independent RPM/encoder measurement; high-resolution crank-angle sensing; synchronized coil voltage/current acquisition; battery energy/state-of-charge monitoring; chamber force/displacement instrumentation; temperature sensors; vibration monitoring; and common-time-base data acquisition.

Calibration certificates, instrument ranges, accuracy, sampling rates, zero/span checks, sensor placement, and an uncertainty budget should be retained with the raw test data.



13. Required Validation Test Sequence

Recommended stages are: magnetic material/coil characterization; single-chamber static force mapping; dynamic chamber testing; multi-chamber mechanical testing; unloaded crankshaft operation; dynamometer load testing; generator coupling; P1 baseline; P2 regenerative testing; P3 generator-head testing; thermal stabilization; sustained energy-balance testing; load-step testing; endurance testing; teardown inspection; repeatability testing; and independent reproduction of calculations.

Acceptance criteria should be established before formal tests and should distinguish design targets from experimentally verified results.



14. Independent Validation Criteria

A third-party validation should identify the exact prototype configuration/revision, inspect the as-built system, verify calibration, witness testing, obtain raw synchronized data, independently calculate electrical and mechanical energy, account for storage changes and auxiliaries, quantify uncertainty, reconcile conservation of energy, and document all qualifications.

The phrase “independent validation completed” should only be used after an actual qualified independent reviewer or laboratory has performed and documented the stated scope.



15. Scaling and Commercial Feasibility

Scaling requires validated module performance plus engineering for magnetic saturation, conductor current density, power electronics, thermal rejection, structural loads, vibration, bearings, insulation, fault energy, generator size, redundancy, serviceability, and manufacturing tolerances.

Commercial ratings such as 200–900 kW and multi-MW systems should remain development targets until supported by calibrated prototype data and a defensible scaling model. Larger system-level targets likewise require staged demonstration.

16. Overall Technical Feasibility Finding

MECREGEN is technically feasible for continued engineering development as an electromagnetic reciprocating motor/generator architecture. Its component-level functions are grounded in established electromagnetic, mechanical, and electrical engineering principles, and the documentation provides a coherent basis for prototype design and testing.

This report does not certify self-sustaining or net-positive operation, a specific horsepower/MW output, safety, reliability, regulatory approval, or commercial readiness. Those stronger propositions remain validation items.

Present engineering classification: ARCHITECTURE TECHNICALLY PLAUSIBLE — QUANTITATIVE PERFORMANCE AND CLOSED-LOOP ENERGY CLAIMS REQUIRE INDEPENDENT PHYSICAL VALIDATION.

17. Professional Reliance and Limitation

This report is an engineering review and technical-feasibility assessment prepared from MECREGEN technical documentation. It is not a PE-sealed opinion, accredited laboratory report, or representation that an external engineering firm has completed independent validation. Final certification requires the actual qualified reviewer to inspect the applicable configuration, methods, calibrated measurements, raw data, and calculations within that reviewer's professional scope.

18. Claim Validation Matrix

Claim / Function	Engineering Status
Electromagnetic force produces reciprocating motion.	Supported in principle
Reciprocating motion drives crankshaft.	Supported
Crankshaft drives generator/alternator	Supported
Generator can recharge storage.	Supported
Crank-position-controlled switching	Supported in principle
TIES conversion architecture	Technically plausible
No combustion required in electromagnetic engine	Supported by architecture
Zero direct combustion emissions from engine	Supported by architecture
Magnetic/low-contact bearing friction reduction	Plausible; testing required
Continuous self-sustaining P2/P3 operation	Not yet demonstrated
Continuous net external power after all internal loads	Not yet demonstrated
5,200 hp output	Requires calibrated prototype verification
200–900 kW / MW-scale performance	Requires scaling and prototype validation
1–500 MW deployment	Future system-level target; not presently validated

19. Prototype Acceptance Checklist

☐ Controlled prototype configuration and revision identified

☐ Test plan approved before testing

☐ Pass/fail criteria pre-defined

☐ All material electrical inputs measured

☐ Generator/electrical outputs measured

☐ Torque and RPM measured where mechanical output is claimed

☐ Battery/storage energy change measured

☐ Auxiliary and cooling loads measured

☐ Thermally stabilized interval achieved

☐ Raw synchronized data retained

☐ Calibration certificates current

☐ Measurement uncertainty calculated

☐ Energy balance independently recalculated

☐ Repeatability demonstrated

☐ Exceptions and anomalies disclosed

☐ Independent reviewer/lab scope documented

20. Engineering Reviewer Sign-Off Template

For completion only by the actual reviewer within the scope performed.

Reviewer / Firm: _____

Professional Discipline / License (if applicable): _____

Prototype Configuration Reviewed: _____

Test Date(s): _____

Raw Data / Calibration Records Reviewed: _____

Material Qualifications / Exceptions: _____

Conclusion: _____

Signature / Date: _____

21. Documentation Basis

- MECREGEN Technical White Paper / Engineering Review Materials
- MECREGEN Tri-Internal Energy System (TIES) Volume I, Chapter 3 Architecture
- MECREGEN TIES Institutional Engineering White Paper
- MECREGEN Prototype, Testing & Validation Due Diligence Package
- MECREGEN Annual Technology, Engineering & Prototype Validation Certificate Package
- MECREGEN Independent Prototype Validation / Third-Party Laboratory Test & Technical Certification Readiness materials
- U.S. Patent 7,557,473 B2 — Electromagnetic Reciprocating Engine